



Addendum

RIVERVIEW PARK TENNIS COURTS LIGHTING UPGRADE

1. Correction: There is a total of 48 fixtures, not 44, on the 7 courts.
2. Existing 40' tall concrete poles will be used in the lighting upgrade. No poles shall be installed within the perimeter of the fences.
3. Existing electrical voltage for Courts 1, 2, 3 is 277 volts. All existing fixtures on Courts 1, 2, 3 are 1000 watt metal halide. Existing electrical voltage for Courts 4-7 is 480 volts. All existing fixtures for Courts 4-7 are 1500 watt metal halide.
4. Poles 3 and 4 each currently have 8 metal halide fixtures on them. Poles 1, 2, 5, 6, 7, 8, 9, 10 each have 4 metal halide fixtures on them.
5. Please quote the quantity of fixtures required to meet the foot candle levels for Class III lighting.
6. Integral drivers are required for fixtures.
7. New lighting controls for the fixtures is not required but should be listed as an option. At a minimum, installed lighting should utilize existing controls.

